

**BOQ for repairing & launching of Anchor Pontoon of ID-IV During the Year -2010-11
(L- 6.0M, B- 2.0M, DFT- 1.5M,)X2**

Sl. No.	DESCRIPTION OF WORK	UNIT	QTY	RATE	AMOUNT
1	Ultrasonic testing to be made of hull ,side & deck plate and welding joint testing.	Spot	50		
2	Cropping & renewal of damage MS plate, angle, winch plateform,"A" bracket and angle plate, under water & deck plate / bollard /main hole cover nut & bolt / rubber gasket.	ton	0.5		
3	Entire outer and inner under water hull plates, side plates, deck plate & other fitting to be chipped, wire brushed and cleaned.	Sqm	180		
4	Under water hull plate & side plate to be painted by 3- coats as per painting scheme from keel to water level (40X3 =120Sqm)	Per sqm per coat	120		
5	Ship side plate from LWL to deck level & other fitting painted by 2 coats as per painting schedule (50X2 =100Sqm)	Sqm	100		
6	Entire inner hull plates, side plates, deck plate & other fitting painted by 2 coats as per painting schedule (90X2 = 180Sqm)	Sqm	180		
7	Servicing & repairing of anchor winch,Pulley & All fittings by welding / Steel Nut, Bolt, Washer				
(a)	Labour charge	No.	1		
(b)	Cost of spare (Actual + 10%)	L-S			
8	Assembly, launching & commissioning of Anchor pontoon of ID-IV. With all accessories i.e winch,winch plateform,"A" bracket and angle plate etc.(From IWAI TERMINAL TO RIVER)	L-S			
	Total				