

**SUB : NOTICE INVITING QUOTATION FOR CONSTRUCTION OF DRUM
BUOY WITH RCC SINKER FOR LAYING IN SUNDERBAN
WATERWAYS.**

Sealed quotations are invited for Construction of Drum buoy with RCC Sinker for laying in Sunderban Waterways. as per annexure enclosed and Terms & conditions given below.

TERMS & CONDITIONS

1. The price may be quoted including all the costs such as labour, materials, VAT/Taxes on materials required, transportation, shuttering, welding etc. No other extra charges will be entertained.
2. The work shall be completed within 15 (Fifteen) days from the date of issue of the work order.
3. 100% payment will be released by cheque only after delivery and checking of constructed materials.
4. In case of delay in supply, liquidated damage @ 0.1% per week subject to a maximum of 5% will be charged on the total cost.

Sealed quotation should reach to IWAI, Kolkata Office on or before 21.07.2009 at 1500 hrs. and will be opened on same day at 1530 hrs.

IWAI reserves the right to accept or reject any or all applications without assigning any reasons and no correspondence will be entertained in this regard.

Encl : As stated.

Director

**CONSTRUCTION OF DRUM BUOY WITH RCC SINKER FOR
LAYING IN SUNDERBAN WATERWAYS**

Sl. No.	Item particulars and specification	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1	Construction and supply of 21" dia & 38" height barrel buoy fabricated with Mild Steel Flat bars (40 mm x 6mm) 200 liters old steel barrel fitted with 10 mm clamp, 5/8 swivel including supply of 20 meters length 10 mm dia mild steel wire rope including construction and supply of 2' x 2' x 1'6" RCC sinker with specific grade of cement concrete (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) and using Mild Steel bar of 20 mm dia, 16mm dia & 8 mm dia labour charges at BISN jetty.	Nos	10		
	TOTAL				

Amount quoted in words (Rupees
.....)

N.B:- Drawings & Specification may be collected from the IWAI, Kolkata, Regional office.